



सत्यमेव जयते



Ref. ठामपा/काअ/पू.प्र/219

Date : 29/ 8 / 2023

दरपत्रक नोटीस

विषय: नविन उपनगरिय स्थानक विकसित करणे कामाअंतर्गत प्रादेशिक मनोरुग्णालयामध्ये महिला कक्ष क्र.१८ समोर नविन पाण्याची टाकी उपलब्ध करणेबाबत.

अंदाजखर्च:-१९८०००/- (१६७६०८ + १८%GST)

वरील विषयांकीत कामाकरीता ठाणे महानगरपालिका, सार्वजनिक बांधकाम विभाग, संबंधित क्षेत्रात मान्यताप्राप्त ठेकेदारामार्फत टक्केवारी दराची मोहरबंद दरपत्रके मागवित आहेत. सदर कामाची दरपत्रके दि. ३१.०८.२०२३ ते ०८.०९.२०२३ या कालावधीत सकाळी ११.०० ते सायंकाळी ४.०० वाजेपर्यंत ठाणे स्मार्ट सिटी लि.कार्यालय, दुसरा मजला, ठाणे महानगरपालिका मुख्यालय, ठाणे येथे स्विकारण्यात येतील. मुदतीनंतरच्या दरपत्रकांचा विचार केला जाणार नाही. जी.एस.टी. नंतर लागू झालेल्या कराच्या बोज्याचा विचार करुन आपले दरपत्रक सादर करण्यात यावे. प्राप्त दरपत्रके शक्य झाल्यास दि.०८.०९.२३ रोजी सायंकाळी ५.०० वा उघडण्यात येतील. याची नोंद घ्यावी.

अटी:-

- १.महाराष्ट्र शासना कडुन देण्यात आलेले सार्वजनिक बांधकाम विभागाचे नोंदणी प्रमाणपत्र.
- २.ठाणे महानगरपालिकेकडे काम पुर्ण केल्याचा दाखला.
- ३.जी.एस.टी. प्रमाणपत्र

सोबत अंदाजखर्च

(धनाजी मोदे)

कार्यकारी अभियंता

सार्वजनिक बांधकाम विभाग
ठाणे महानगरपालिका, ठाणे

विषय :- नविन उपनगरिय स्थानक विकसित करणे कामाअंतर्गत प्रादेशिक मनोरुग्णालयामध्ये महिला कक्ष क्र.१८ समोर नविन पाण्याची टाकी उपलब्ध करणेबाबत

SCHEDULE -B

Sr.No	Item No	Item Description	Unit	Qty	Rate	Amount
1	23.12	<p>Providing structural steel work in hollow section of various thickness and sizes in square, rectanular and round shape from 25mm to 450mm section as per IS 4923 YST 310 Grade produced from iron ore and blast furnace route etc. as per detailed designs and drawing or as directed including cutting, fabricating, hoisting, erecting, fixing in position, making riveted/bolted/ welded connections and painting complete.</p>	M.T.	0.1	124894.40	12489.44
2	38.41	<p>Providing and fixing self supporting steel roofing system for a Godown or alike made up of structural grade steel sheet of 912 millimeter width (tolerance +/- 2 millimeter), moulded at site using mechanical press dies to the desired curve and shape to form 605 millimeter wide interlocking panels . The interlocking panels shall be pressed to close the seam forming water tight joints for a span of 15.30 meter having arch rise as 3.06 meter, arch length 17.75 meter. The base material made up of imported galvalume steel complying to ASTM A792 having base metal thickness of 0.80 millimeter (tolerace + / - 0.02 millimeter) with alloy coating AZ 150 and paint coating of regular modified polyster , top coat 25 micron and bottom coat 12 micron as per approved colour , including fixing hangers , clamps etc.as may be necessary of Proflex standard, including fixing sky light of 2 millimeter thick polycarbonate sheet of size 2' x 7' and turbo ventilator of 24" diameter to be installed at every 30 feet along the length of roof including finishing, testing and cleaning etc. complete.</p>	Square Meter	12	2377.2	28526.40


3	42.54	Providing and fixing H.D.P container one piece moulded water tank made out of low density polythylar and built corrugation including of delivery up to destination hoisting and fixing of accessories such as inlet, outlet overflow of all tanks capacity above 1000 to 20,000 litres	litre	10000	11.5	115000.00
4	42.98	Providing and laying in trenches 32 mm dai. uPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	One running meter	12	483	5796.00
5	42.97	Providing and laying in trenches 25 mm dai. uPVC pipe including necessary excavation, fittings. Refilling trenches etc. complete. Including removing existing pipe line if necessary and conveying and stacking the same in PWD chowky or as directed etc. complete.	One running meter	12	483	5796.00
Grand total						1,67,607.84

Say 1,67,608.00

वरील रकमेमध्ये जीएसटीचा समावेश नाही. दरपत्रक सादर करतेवेळी याची नोंद घेऊन दर सादर करावेत.

कोटेशन-----%ABOVE/BELOW

सदर कामाची दरपत्रके दि. ३१.०८.२०२३ ते दि.०८.०८.२०२३ या कालावधीत सकाळी ११.०० ते सायंकाळी ४.०० वाजेपर्यंत ठाणे स्मार्ट सिटी लि.कार्यालय, दुसरा मजला, ठाणे महानगरपालिका मुख्यालय, ठाणे येथे स्विकारण्यात येतील. प्राप्त दरपत्रके शक्य झाल्यास दि.०८.०८.२०२३ रोजी सायंकाळी ५.०० वा उघडण्यात येतील.


(धनाजी मोदे)

कार्यकारी अभियंता
सार्वजनिक बांधकाम विभाग
ठाणे महानगरपालिका, ठाणे